



HPF 163A

### FINISH SCHEDULE

ROOM #	FLOOR FIN.	BASE	VALS				CELLS	REMARKS
			N	E	S	W		
201	EXIST.	EXIST.			PATCH MATCH	PATCH MATCH	EXIST.	PATCH TO MATCH C WINDON & DOOR - SAND SMOOTH
202			P.C. IMP. BOARD					
203			PATCH MATCH					
204								
205								
206					P.C. IMP. BOARD			
207								
208	1/2" SUB-FLOOR		PATCH MATCH		PATCH MATCH			PATCH TO MATCH C BASES WHERE WINDON'S ARE LEAVED
209	WOOD		P.C. IMP. BOARD					
210					P.C. IMP. BOARD			
211			PATCH MATCH					
201	1/2" SUB-FLOOR		IMP. BOARD	IMP. BOARD	IMP. BOARD	IMP. BOARD	IMP. BOARD	NO SKIN COAT
202					EXIST'G STUDS			ON 1/2" IMP. BOARD
203					EXIST'G STUDS			
204					IMP. BOARD			

### Door Schedule

DOOR #	DESCRIPTION	MANUF.	SIZE WxH	R.O. WxH	HARDWARE	REMARKS
1	TOL SWINGING PATIO DR. (WOOD)	POZZI	33 1/2" x 68"	33 1/2" x 68"	A	ALUM. SILL W/ WEATHERSTRIP & THERMO-pane INSULATION
2	TOL SLIDING PATIO DR. (WOOD)	POZZI	36 1/2" x 80"	36 1/2" x 80"	A	
3	TOL SWINGING PATIO DR. (WOOD)	POZZI	36 1/2" x 80"	36 1/2" x 80"	A	
4	TOL SWINGING PATIO DR. (WOOD)	POZZI	36 1/2" x 80"	36 1/2" x 80"	A	
5	EXTERIOR S.C. WOOD PUSH DR.	BRISCO	36" x 78"	36" x 78"	A	TRIM DR. TO OPENING ALUM. SILL W/ WEATHERSTRIP
6			36" x 78"	36" x 78"	B	ALUM. SILL W/ WEATHERSTRIP CUT TO FIT OPENING
7	BRISCO BIRCH 1/2" LABEL DOOR	BRISCO	36" x 78"	36" x 78"	B	INTL KNOCK DOWN BR. KIT K.D.I. (BRISCO) PR. = 15 GA.

**NOTES:**

- ALL DOORS @ EXT. TO BE PRE-HUNG WOOD LAMINATED JAMB
- WEATHERSTRIP, ALUM. SILL & INSUL. GC. TO BE PRIN'D (EXT.)

### Hardware Schedule

A - SCHLAGE 'A' SERIES, ASD PD  
PLYMOUTH - BRASS KNOB & TURN W/ KEY  
605 FINISH

B - PASSAGE, SCHLAGE 'A' SERIES, A105  
PLYMOUTH - BRASS KNOB & TURN  
605 FINISH

Received for record in Jamestown, RI  
 Apr. 1, 2000 at 10:48 AM  
 Alvin DeBari Town Clerk  
 32

## SECOND FLOOR PLAN

# SEA CHALET RENOVATIONS

JAMESTOWN, RHODE ISLAND

DATE: 21 JUNE 1990  
 DRAWN:  
 REVISIONS:

**2nd FLR. PLAN**  
 Finish & Door Sch.

**A.2**

ESTES & CO  
 ARCHITECTS  
 401.846.3300

79 THAMES ST  
 NEWPORT, RI  
 02840-2536